



SOFTWARE RELEASE NOTES

WAP-EN1200C

Version: 1.2.0.15

Release Date: June, 2017



Revision Summary:

Software Version	Description	Release Date
1.2.0.15	Release# 20170412	June, 2017
1.1.0.14	Release# 20160914	12/14/2016
1.0.1.2	Release # 20160520	06/08/2016
1.0.0.5	Release # 20160428	04/28/2016
1.0.0.3	Release # 20150819	08/19/2015
1.0.0.2	Release # 20150810	08/10/2015
1.0.0.1	Release # 20150730	07/30/2015

New Features:

- New version of NMS feature (Version: 1.3.1.0) available
- Now supports Fast Roaming feature (802.11r/k)
- Now supports Captive Portal guest data limitation
- Now supports Google Maps
- Now supports SNMP on NMS mode
- Now supports Spanning Tree Protocol (STP)
- Now supports Comtrend WifiXtend feature
- Now supports TR-111 (STUN client)

Changes and Fixes:

- Fixed the NMS Smart Roaming setting where “default values” was not an icon in the edit page

Known Issues:

- None

Access Default Settings:

AP LAN IP Address: 192.168.2.1

Username/Password: admin/admin

Prior Releases:**1.1.0.14**

- Added TR-069 feature
- New version of NMS feature (version: 1.2.1.0) available
- Added Captive Portal feature
- Optimized the “Save and Apply” function

- Revised the behavior that did not check the MAC
- Fixed some of the SSID not getting the correct settings when all 16 SSIDs with WPA2 security were enabled
- Revised the NMS function for monitoring SSID on the web GUI
- Changed the SNMP Object Identifiers (OID) to 3136
- Extended the HTTP log-in timeout during idle
- Fixed the AP behavior in NMS mode where it would self-check itself as one of the managed AP's

1.1.0.2

- Changed FW version name from 1.0.0.5 to 1.0.1.2
- Guest network feature is now available in standalone mode in addition to managed mode

1.0.0.5

- Fixed system clock
- Fixed when set to AP mode, the VLAN could not be configured
- Fixed the 5GHz network dropping when the WDS feature used to connect between APs. It would randomly drop and would require a reboot of the system to recover
- Fixed WiFi performance issue
- Fixed NMS 5GHz monitoring feature showing a value of "4320" when in idle time.
- Changed Web GUI model name to "WAP-EN1200C"
- Changed Web GUI Company name to "Comtrend Corporation"

1.0.0.3

- Fixed when the scan feature would stop scanning when doing a scan or refresh. No information will be shown under the active section

1.0.0.2

- Fixed VLAN tagging feature
- Fixed HTTPS access

1.0.0.1

- Fixed NMS v1.2 feature

Upgrade Procedure:

1. Upgrade Software

- a. Assign a 192.168.2.x/24 static IP address on your computer. Where x is a number in the range of 3-100.
- b. Open a web browser, connect to 192.168.2.1, and login with username **admin** and password **admin**.
- c. Click on **Advanced**→**Update Firmware**: Software Upgrade. Click on "Browse" button

- d. Locate and double click on the appropriate Comtrend software image
 - e. Click on "Update" button. You will be informed that the product will become unresponsive and to not turn off or unplug the product, click "OK". New window will pop-up showing the progress of uploading the software. Upon completion, the GUI page will be redirected to the log-in page.
2. Verify
- a. Log-in to the GUI.
 - b. Information section of the GUI shows the "Firmware version". Verify that the latest code reflects: 1.2.0

Technical Support:

For technical support contact your Sales Engineer or Comtrend Technical Support at 949-753-9640, Option 3. You can also submit questions and comments at <http://us.comtrend.com/contact-us/>

RMA Request

An RMA can be initiated at <http://customersupport.comtrend.com/>

The contents of this document are current as of the date of publication. Comtrend Corporation reserves the right to change the content without prior notice. In no event will Comtrend Corporation be liable for any damages or for commercial losses resulting from information contained in this document.